6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Constructing Anglo-Hindustani School at Bangalore.

Items of work	Per	Rate	Quantity	Cost	Total
Earthwork excavating and filling basement	C. yd.		180		
Metal concrete in chunam	C. ft.		1,721		
Burnt stone in mortar, including bond slabs, 6' apart in foundation.	"		5,620		
Burnt brick in clay superstructure	"		5,027		
Wire cut bricked arch work	"		67		
Burnt stone slabs, 6" thick, R. D.	S. ft.		945		
Plastering with chunam	Sq.		114·80		
White and colour washing	"		114·80		
Teakwood doors panelled with iron fastenings, etc., complete.	S. ft.		450		
Teakwood windows with 1½" shutters with single shutters, half panelled and half covered with iron fastenings, hinges, etc., complete.	"		345		
Teakwood rectangular glazed ventilators	"		96		
Do circular do	"		12½		
Silicate painting	Sq.		17·00		
Cut stone pillars with base and nicely dressed	Each		8		
Brick masonry pillars do	"		8		
Teakwood wrought and put up with wood oiling ...	C. ft.		209·60		
Do beams	"		53·80		
Ridge tiles set in mortar	R. ft.		133		
Pukka terracing for hall	Sq.		6·14		
Roofing with 1st Class Mangalore tiles, over teak reepers, complete.	"		30·75		
Flooring with Cuddapah slabs, over 3" concrete and cement pointed.	"		24 84		
Ornamental parapet wall, 3" high	R. ft.		21		
Chunam borders and blocking course	"		80		
Ordinary parapet wall, 4½" thick with 9" piers	"		84		
Ionic entablature, complete	"		55		
Cornice, 12" × 12"	"		422		
Preparing Ionic and Doric, Capitals	Each		12		
Preparing Ionic and Doric bases	"		21		
Moulded archivalts for arches	R. ft.		31		
Preparing panels and ornamental flower works, etc. ...	L. S.		Rs.		
Chunam pointing	"		85		
Eave boards, 9" depth, ornamental	R. ft.		72		
V shaped drain around building with Cuddapah slabs ...	S. ft.		300		
Valley planks, ¾" thick	"		156		
Mortar bonds over valley with nice mortar ...	R. ft.		52		
Zinc sheet to valley	S. ft.		156		
Burnt brick in chunam	C. ft.		1,156		

S. SRINIVASA AIYAR,
Executive Engineer.

MYSORE DIVISION.

Dated 3rd February 1919.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 3rd March 1919, for reconstructing the Central Police Station at Doddapeta, Mysore City. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (550) five hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for reconstructing the Central Police Station, Doddapetta, Mysore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever, for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for reconstructing the Central Police Station at Doddapetta, Mysore City.

Serial No.	Items of work	Per	Quantity
1	Earthwork excavation	C. yd.	311
2	Concrete in mortar	C. ft.	2,181
3	Basement filling with earth, watering and tamping with available earth ...	C. yd.	186
4	Burnt brick in chunam F and B.	C. ft.	6,333
5	Do superstructure	"	8,030
6	Do segmental arch work	"	113
7	Do flat arch work	"	280
8	Burnt stone slabs 6" thick roughly drssed	S. ft.	600
9	Dressing 2 lines neatly	"	247
10	Teakwood work wrought and put up with oiling	C. ft.	423·90
11	Plastering with chunam	Sq.	135·00
12	White and colour washing	"	135·00
13	Teakwood doors, panel shutters with bolts, nuts, hinges and fastening, etc., complete.	S. ft.	373
14	Fittings for the above	Each	10
15	Teakwood windows, venetioned shutters outside and glazed shutters inside, hinges, bolts,, iron bars, etc., complete.	S. ft.	367
16	Teakwood ventilators with glazed shutters and iron bars, etc., complete ...	"	84
17	Ornamental work in front of windows	Each	12
18	Terrace brick on edge	Sq.	30·95
19	Cornice 9" thick	R. ft.	353
20	Silicate painting	Sq.	27·49
21	Basement cornice	R. ft.	170
22	Ornamental work in front of entrance such as rosettes, etc.	Each	8
23	Do cresting over archways	"	3
24	Forming mouldings bottom and top of pillars	"	12
25	Roofing with Mangalore tiles on teak reepers, nails, etc.	Sq	4·88
26	Archvolts of arches	R. ft.	56
27	Teakwood eave board with painting 10"×1"	"	25
28	Do do 3"×1"	"	107
29	Ornamental flower caps and case of side pillars corners	Each	6
30	Teakwood ornamental brackets for sunshades	"	22
31	Burnt brick in chunam coping including plastering	R. ft.	141
32	Flooring with square tiles over 3" concrete and cement pointing ...	Sq-	17·46
33	Do Cuddapah slabs on 3" concrete bed and cement pointing ...	"	7·27
34	Teakwood hair case complete	Lump sum	...
35	Do almirahs with shutters, etc., complete.	Each	2
	First floor.		
1	Burnt brick in chunam superstructure	C. ft.	5,346
2	Do segmental arch	"	70
3	Do flat arch work	"	404
4	Burnt stone slabs 6" thick roughly dressed	S. ft.	124
5	Teakwood work wrought and put up with ceiling	C. ft.	388·13
6	Plastering with chunam	Sq.	114·0
7	White and colour washing	"	114·0
8	Teakwood doors, panel shutters with bolts, nuts, hinges fastening, etc., complete.	S. ft.	288
9	Fittings for the above	Each	9
10	Teakwood windows, venetioned shutters outside and glazed shutters inside, hinges and bolts, etc., complete.	S. ft.	353
11	Teakwood circular ventilators with glazed shutters, etc., complete ...	"	56
12	Ornamental work in front of windows	Each	16
13	Iron gate complete with painting for lock-up	"	4
14	Terrace brick on edge	Sq	28·17
15	Lovey cornice with Cuddapah slabs and plastered over with rough stone brackets, etc., complete.	R. ft.	248
16	Cornice 9" thick	"	49
17	Silicate painting	Sq.	24·5
18	Ornamental work in front of entrance such as rosettes	Each	8
19	Ornamental cresting over archways	"	3
20	Forming moulding bottom and top of pillars	"	10
21	Roofing with Mangalore tiles on teak reepers and nails, etc., complete for sunshades.	Sq.	4·88
22	Arch volts of arches	R. ft.	56
23	Teakwood cave boards with painting 10"×1"	"	25
24	Do do $3\frac{1}{2}$"×$\frac{1}{2}$"	"	107
25	Ornamental flower cars and case of side pilasters corners	Each	6
26	Teakwood ornamental brackets for sunshades	"	22
27	Flooring with square tiles and cement pointing	Sq.	24·25
28	Brick knogged partitions walls with plastering, etc., complete	S. ft.	620
29	Cast iron rain water pipes	R. ft.	374
30	Constructing tower with Chamundi stone pillars masonary dome lovey cornice and complete.	Each	1
31	Ornamental parapet walls 2' high with brick in chunam and plastered over with mortar.	R. ft.	315
32	Ornamental dases	Each	7
33	Ornamental small towers with dome cornice, etc., complete	"	3
34	Ornamental pedement with creepers and gandaberunda and etc., complete ...	"	5
35	Teakwood almirahs with shutters, etc., complete	"	2
36	Unforeseen	Lump sum	...
37	Electric refittings	"	...
38	Water-supply	"	...
39	Cleaning and levelling	"	...

Dated 3rd February 1919.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 4th March 1919, for constructing a Village Elementary School at Belagola, Seringapatam Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (100) one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Village Elementary School at Belagola, Seringapatam Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineeer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing a Village Elementary School at Belagola, Seringapatam Taluk

Items of work	Per	Quantity
Clearing site and levelling ground	L. S.	...
Earthwork excavation	C. yd.	36
Burnt brick in clay	C. ft.	3,271
Do in chunam	"	263
Burnt stone slabs dressed and fixed	S. ft.	285
Chunam plastering	Sq.	46·00
White and colour washing	"	46·00
Honneywood work wrought and put up	C. ft.	75·14
Roofing with 1st class Mangalore tiles on teak reepers, etc., complete ...	Sq.	15·25
Mangalore ridge tiles set in mortar and cement pointed	R. ft.	55
Chunam borders at gable ends	"	108
Cutting grooves in stone uprights	Each	8
Coping with burnt brick in chunam and plastering	R. ft.	53
Capitals to gate pillars	Each	2
Flooring with gravel including cowdung washing, etc., complete	C. yd.	25
Honneywood battened doors, planks 1¼" thick including frames and hinges, etc., complete 4"×3".	S. ft.	98
Honneywood battened windows with 6 iron bars ¾" dia., etc., complete ...	"	81
Mangalore ventilating tiles	Each	8
Painting chocolate	Sq.	5·28
Wood oiling 2 coats	"	7·00
Honneywood gate shutters including painting iron works and fitting, etc., complete.	S. ft.	22
Providing black boards	"	4·9

Dated 3rd February 1919.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 4th March 1919, for constructing a Village Elementary School at Manchanahalli, Yedatore Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Village Elementary School at Manchanahalli, Yedatore Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing a Village Elementary School at Manchanahalli, Yedatore Taluk, Mysore Division.

690

Items of work	Per	Quantity
Clearing site and levelling the ground	L. S.	...
Earthwork excavation	C. yd.	36
Burnt brick in clay	C. ft.	3,271
Do chunam	"	268
Burnt stone slabs dressed and fixed	S. ft.	285
Chunam plastering	Sq.	46·00
White and colour washing	"	46·00
Honney wood work wrought and put up	C. ft.	75·14
Roofing with 1st class Mangalore tiles on teak reepers, etc., complete	Sq.	15·25
Mangalore ridge tiles set in mortar and cement pointed	R. ft.	55
Chunam borders at gable end	"	108
Cutting grooves in stone uprights	Each	8
Coping with burnt brick in chunam and plastering	R. ft.	53
Capitals to gate pillars	Each	2
Flooring with gravel including cowdung washing, etc., complete	C. yd.	25
Honney wood battened doors, planks 1½" thick including frames and hinges, etc., complete (4"×3").	S. ft.	98
Honney wood battened windows with 6 iron bars ⅝" dia. etc., complete	"	81
Mangalore ventilating tiles	Each	8
Painting chocolate	Sq.	5·28
Wood oiling 2 coats	"	7·00
Honney wood gate shutters including painting iron works and fittings, etc., complete ...	S. ft.	22
Providing black boards	"	4·9

A. PUTTUSAMAIYA, *Executive Engineer.*

KADUR DIVISION.

Dated 9th February 1919.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 28th February 1919, for constructing Police Lines and Pukka Station at Kalasapur, Chikmagalur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st December 1919.

2. The plans detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Police Lines and Pukka Station at Kalasapur, Chikmagalur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of detailed quantities for constructing Pukka Police Station at Kalasapur, Chikmagalur Taluk.

No.	Items of works	Per	Quantity
1	Earthwork excavating, foundation and filling in basement	C. yd.	67
2	Chunam concrete	C. ft.	557
3	Rough stone in clay.	"	1,602
4	Burnt brick in clay	"	1,505
5	Burnt brick in mortar	"	436
6	Burnt stone slabs, 6" thick	S. ft.	238
7	Plastering with mortar	Sq.	39·06
8	Burnt brick in mortar coping	R. ft.	67
9	White and color washing	Sq.	39·06
10	Honneywood work wrought and put up	C. ft.	49·00
11	Roofing with 1st class Mangalore tiles on teak reepers	Sq.	11·20
12	Ridge tiles set in mortar	R. ft.	40
13	Teakwood ceiling plank, ½" thick, including fixing	S. ft.	210
14	Honneywood door battened with necessary iron fittings, etc.	"	83
15	Teakwood door for lock-up with iron bars, etc., as per type design	"	49
16	Honnewood wiudows with iron bars	"	35
17	Honneywood ventilators with expanded metal and ¾" iron bars	"	11
18	Honneywood eave board with pa inting	R. ft.	128
19	Wood oiling to wood work	Sq.	6·00
20	Silicate painting and coated with varnish	"	5·81
21	Tarring wood work	"	3·00
22	Flooring with 1st class Mangalore tiles, 9" square, over 3" concrete bed and cement pointed.	"	3·92
23	Wooden railings of teakwood as per plan	R. ft.	52
24	Teak gate ordinary with shutters, including iron fittings, etc., complete ...	S. ft.	16
25	Flooring with Cudapah slabs, over 3" concrete bed on cement pointing ...	Sq.	1·52
26	Cement pointing	"	4·12
27	Constructing V-shaped drain with cement plastering ...	R. ft.	100
28	Gravelling and consolidating with lead	C. yd.	12
29	Teakwood finials at ends of gables	No.	2
30	Binding walls on roof	R. ft.	48
31	Clearing site and levelling ground	Lump	sum Rs.